

PNWS AWWA, Eugene Oregon
May 8, 2014



Crandall Reservoir: A Case Study

Utility Perspectives on the Will Crandall Reservoir and Pump Station Project

Tyler Wubbena, PE, City of Hillsboro




Acknowledgements

- Kevin Hanway, City of Hillsboro
- Brad Phelps, CH2M HILL
- Ward-Henshaw Construction
- City of Hillsboro Staff

Outline


- Project Background
- Design Objectives
- Water Quality
- Power Components
- Project Funding
- Public Involvement & Outreach

Project Background



Project Background: Hillsboro Water System

- 2 Existing Reservoirs: 5.6 MG and 15 MG
- 9 PRV Connection Points




Project Background

- CMGC Project Delivery
 - 10 MG Partially-Buried Water Tank
 - 15 MGD Booster Pump Station
 - 800 kW Generator
 - 88 kW Hydro Turbine
 - Rechlorination
 - Mixing System
-
- 24th Street Reservoir – Rechlorination and Mixing System



Project Background - Site Features



Design Objectives

Design Objectives

- ☑ Meet distribution storage requirements
- ☑ Maintain water quality
- ☑ Provide backup power and water supply in an emergency
- ☑ Accommodate future ASR
- ☑ Accommodate future pump station expansion
- ☑ Maximize opportunities for flexibility in operation

Design Objective: Emergency Supply

- Dedicated connection on PS header for Blivet fill station



Design Objective: Future ASR and High Pressure Zone Pump Station


Existing

- Pump Station
- Backup Power
- Rechlorination
- Pump to waste basin
- SCADA
- Piping



Design Objective: Operational Flexibility

- “Davis” Dump Valve
- 2014 NTL Main Break



Project Funding

Project Funding

- System Development Charges (SDC's)
- Water Fund (rates)
- PGE Dispatchable Standby Generation (DSG) Grant
- Energy Trust of Oregon (ETO)
- Oregon Infrastructure Funding Authority (IFA) Grant

Project Funding

- PGE Dispatchable Standby Generation (DSG) Grant
- Hillsboro received \$132,000 for DSG grant
- Note: Hillsboro will receive future O&M saving through the DSG partnership

Project Funding

- Energy Trust of Oregon (ETO)
- Applied for two separate grants
 1. 24th St Reservoir Rechlorination and Mixing
 - Initial grant award \$45,842
 - Reduced to \$43,843 after validation
 2. Crandall Reservoir Rechlorination and Mixing
 - Initial grant award \$74,029
 - Still under validation testing of system



Project Funding

- Business Oregon / Infrastructure Finance Authority Grant
- Previously City of Hillsboro waived a SDC fee for economic development
- Hillsboro received an IFA Grant project design
- Hillsboro required to provide matching funds
- Prominent signage requirements

Water Quality

Water Quality/Energy Savings



- Longer residence time \Rightarrow Less Pumping
- Maintaining chlorine residual with long residence times in reservoirs
 - Field tests to evaluate rechlorination
- CFD to evaluate mixing & sampling
- Incorporation of tablet chlorinator into the reservoir and pump station design

Water Quality/Energy Savings


- *Paradigm shift* in reservoir storage time and water turnover BMP's
- Traditional BMP – 3 day average turnover
- City of Hillsboro – up to 30 days at Crandall and 24th Street Reservoirs




Storage Requirements: Fill and Draw Concepts



Desire to modify current operation
and operate fill/draw cycles less
frequently



Water Quality: Extended Storage Validation – 24th St Reservoir



Water Quality: Conclusion

- Extended Storage Validation
 - 24th Avenue Validation Testing Completed
 - 5 trials: 14, 21, 21, 30, and 29 days storage
 - Mixing, Cl₂ rechlorination, and addition of water part of extended storage strategy
 - No THM or HAA₅ violation
 - Extended storage successful up to 30 days
- Crandall Validation – postponed to Fall 2014

Power Components

Power Components: Overview

- Utility Power Connection
- Backup Generator
 - Power for pump station
 - PGE DSG participation
- Micro Hydro
 - Converting head on inlet to reservoir
- Solar Panels (future)
- Energy Savings in Design
 - LED lighting, outside air ventilation, etc.

Power Components: Backup Generator

- 800 kW generator
 - Oversized for needs at pump station – accommodate future expansion
- 3,000 gal fuel storage



Power Components: Backup Generator & PGE DSG

- Supply power to pump station **AND** backfeed the power utility (PGE)
 - Parallel switching device
- PGE can operate generator remotely
 - PGE can meet peak power requirements for FERC
 - PGE can defer construction of another peak power supply

Power Components: Backup Generator & PGE DSG


- City has first right of refusal for generator use during an emergency
- Generator is exercised under full load during monthly testing
- Win-Win for City
 - PGE pays all maintenance
 - PGE pays all fuel
 - Monitored 24 hours/day

Power Component: In-Conduit Hydropower

- Decrease on-site utility costs
- Convert potential energy into electricity
- Take advantage of constant flow and head to maximize turbine efficiency and output
- Access off-the-shelf pump technology
- Hillsboro is a leader in sustainability

Power Components: In-Conduit Hydropower

- Supply pressure from JWC at delivery point: 125 psi – 130 psi
- Only about 10psig is needed to fill the reservoir .
- We need to “break” the excess pressure of 120psig
 - Pressure Reducing Valve (PRV)
 - Hydroturbine
- Use MicroHydro when reservoir is filled
- Power generated is supplied to the grid
 - Net metering agreement with PGE



Reservoir Pump Operations

- Crandall Reservoir filling cycle volume: 5MG
- Crandall Reservoir water surface elevation level (WSEL) range: 194 to 210
- Duration of Reservoir fill cycle: Depending on seasonal demands and water quality requirements, approximately 2.5 days every 3 weeks
- Nominal Discharge rate of hydropower equipment: 2MGD (3.1cfs)
- Average NTL pressure: 130psig
- Net available head: Depending on NTL pressure and Reservoir WSEL, expected to vary between 250 and 325 feet

Energy Output


- Rated turbine-generator output: 74kW
- Rated turbine-generator rated eff: 71%
- Energy production: 60,000kWh/year
- Energy output: 480 vac, 3-phase, 60Hz
- Net-metering arrangement with Portland General Electric (PGE)



FERC Small Conduit Facility Exemption Requirements

- Utilizes hydroelectric potential for power generation
- Located on non-Federal lands
- Installed generating capacity of less than 40MW
- Not an integral part of a dam
- Does not rely upon construction of a dam
- Discharges the water it uses for power generation into a conduit and directly to a point of municipal consumption

FERC Permitting: City of Hillsboro Water Distribution Network



FERC Exemption Permit Timeline (approximately 19 months)

- Dec. 12, 2011 – Initial Consultation Document sent to over 50 stakeholders
- Jan. 17, 2012 – Initial Consultation Meeting open to all stakeholders and the public / beginning of 30-day comment period
- Mar. 13, 2012 – New docket submitted to FERC with all documentation of Initial Consultation
- Apr. 13, 2012 – Comments received from FERC
- Jul. 6, 2012 – Resubmitted docket to FERC
- Sep. 5, 2012 – FERC initiates 60-day public review of docket
- Nov. 14, 2012 – Order Granting Exemption From Licensing (Conduit) issued by FERC
- Jan. – Mar. 2013 – ordered aperture cards and delivered to FERC in Washington D.C.
- Jul. 3, 2014 – Authorization to start construction


FERC Permitting Issues

- Working with Federal staff in Washington DC – long distance, different time zone
- Stakeholder notification process
 - Over 50 stakeholders notified
 - Two responded: ODFW and WRD
- Legacy documentation requirements – Aperture card (think microfiche)
- Selecting the appropriate Water Right for the project

Power Components: Solar Panels

- Planned as part of future activities at the site
- City has experience with solar panels at Evergreen Reservoir site (100 kW) and multiple other locations
- Note: Solarworld is 3 miles from the project site and a water customer of the City

Power Components: Solar Panels



- Array of panels on reservoir and on site

Power Components

- City has the opportunity to generate power 3 different ways at their Crandall reservoir site
 - Diesel backup power generation partnership with PGE DSG program
 - Microhydro offsets pumping costs at Crandall
 - Future solar panels provide a passive power generation opportunity

Public Involvement & Outreach

Design Phase Neighborhood Meeting

- Early planned outreach to neighbors
- Combined with requirements for noise variance requirements with Washing County
- Provided project fact sheets




You are invited to a
Will Crandall Reservoir Project
Neighborhood Update
Thursday, January 12th, 7:00 – 8:00 p.m.
Evergreen Middle School Commons
29850 NW Evergreen Road

Hillsboro Water (HW) is preparing to break ground at the Crandall Reservoir site. Staff will present an overview of the project, and address key topics such as:

- What is the project timeline?
- Why is HW seeking a noise variance for extended hours during the initial construction work?
- Will there be significant traffic impacts from the construction activities?

A 3D model of the future reservoir site will be on display. Project experts will be available to answer questions.

Need more information?
Please call (503) 615-6702.




Design Phase

- Keep Simple
- Open and transparent
- Direction to additional info
- Point of contact



Will Crandall Reservoir Hillsboro's Newest In-Town Storage



Project Status

Construction will begin soon on the Crandall Reservoir Project. Beginning construction activities include mobilization, site prep, and berm construction. Contractors will then begin laying an earthquake resistant foundation using a concrete and deep soil mixing technique.

Construction Variance

Hillsboro Water is seeking a variance from Washington County to extend working hours from the standard 7am – 7pm to a 6 am - 10 pm double-shift schedule for 90 days, which will allow the Contractor to finish the deep soil mixing portion of the project in early summer rather than early fall, resulting in less noise impacting the neighborhood's outdoor summer activities.

Contractors have planned for sound mitigation. Sound barriers such as a perimeter berm and other blockers will be on-site. The generators to be used are insulated and considered "Hollywood Movie Quality." Loud equipment will be angled away from the south and east and placed to maximize distance between the loudest activities and the nearest residences.

Traffic Impacts

There will be some increase of traffic, due to supply deliveries and workers accessing the site. However, there will be a lot less traffic generated than a typical construction site, such as Intel's D1X, because the majority of excavated soils will be kept on site and used in building a berm.

For more Information

Visit our website at www.hillsborowater.org for updates once the Crandall Reservoir Project is underway.

Receive notification e-mails of construction activities by signing up for the Crandall Neighbors Distribution List. Send requests to be added to the Distribution list to: tacys@ci.hillsboro.or.us.

Phone Contacts:

Contractor: For questions about site activity, the Contractor will post a number at the construction site once the project is underway.

Hillsboro Water: For questions about the Crandall Reservoir Project call Tyler Wubbena, Project Manager, or Tacy Steele, Public Information Coordinator, at (503) 615-6702.

Pre Construction Tailgate

*You are invited to a
Tailgate Talk and BBQ*

for the Will Crandall Reservoir Project

**Wednesday, June 29th, 5:00 – 7:00 p.m.,
Reservoir Site: 30585 NW Evergreen Road**

Grab a burger and visit on-site with the primary project people including:

- Project Manager
- Project Designer
- Project Contractor

View a scaled 3D model of the future reservoir site, examine design plans and talk with project experts about design and construction issues.


**Need more information?
Please call (503) 615-6702.**

PRINTED ON RECYCLED PAPER



190 East Main Street
Hillsboro, OR 97123

SUSY VERGHESE
30095 NW EVERGREEN RD
HILLSBORO, OR 97124



Pre Construction Tailgate

- Used tailgate to proactively reach out to local public
- Intercept before construction inconveniences arise
- Show 3D model of finished facility
- Allow public to ask questions in a comfortable environment



Pre Construction Tailgate

- Keep it a fun, family event



Pre Construction Tailgate



Will Crandall Reservoir
Open House

Today, 5:00 - 7:00pm

Public Welcome



Project Blog

- Project blog posted on Water Department website
- Updated every 2 weeks or as required
- Updates included current activities and project facts
- Included current photos of the project

Project Blog (Screen Shot)

- About Us
- Services
- Departments
- Community
- Business Resources
- I Want To...
- SEARCH... >

Departments » Water » Crandall Reservoir Project

BLOG ARCHIVE

[Share & Bookmark](#) Font Size: [-](#) [+](#) [Print](#) [Feedback](#)

May 8th, 2013 Update

Posted Date: 5/8/2013

Reservoir

DN Tanks is on the second week of wrapping the exterior of the reservoir with the 1st of 3 layers of 3/8" galvanized cable. A total of 80 miles of cable will be installed, with a layer of shotcrete (concrete slurry) sprayed over each layer, before the process is complete. Cable is stressed to 14,950 pounds to provide stability to the structure, primarily during earthquakes. The wrapping process is scheduled to be complete by the end of May.

Pump Station

The framing of the roof section is almost complete and the metal roof is soon to be installed. Interior electrical conduit and plumbing are being installed, and an 800kW back-up generator and switch gear have been installed for emergency operation. Interior painting and dry wall are next.



Pump House Construction

STEM Outreach



- Worked closely with Evergreen Middle School STEM Club
- Provided approximately 5 field visits throughout construction
- Hillsboro staff assisted with in class room learning

STEM Outreach

- Coordinated other tours including JWC WTP
- Program very well received by both students and staff
- Excellent example to demonstrate real world engineering



Dedication & Open House

- Decision made to combine the Dedication and Open House on the same day
- Date selected approximately 5 months before the Dedication
- Schedules to coordinate: Mayor, City Manager, Will Crandall, Commissioners, and so on.....
- Commitment from the Contractor to have the site ready on the date of dedication

Dedication



Dedication

- Surprise turn out!
- Pump station is now an auditorium!
- Will Crandall's extended family traveled from multiple states to attend the dedication



Dedication

Will Crandall was honored with the naming of the Reservoir and Pump Station. Will served on the Hillsboro Utilities Commission for 29 years.



Open House

- Similar to the Tailgate, the Open House allowed to public to see the finished reservoir
- Public response was very positive



Questions?



Thank you,

Tyler Wubbena
City of Hillsboro



Weather: 2012 Record Wet Spring

CH2M Asst PM, Jeff Stallard:
Project Weather Expert



Construction: Site

