



# Lake Oswego · Tigard Water Partnership

*sharing water · connecting communities*

## Construction of a New Willamette River Pipe Crossing

May 5, 2016



American Water Works Association  
**Pacific Northwest** Section

MAY THE PNWS-AWWA  
**SOURCE**  
BOISE 2016 **BE WITH YOU**

# Lake Oswego – Tigard Water Partnership

## Construction of a New Willamette River Pipe Crossing

### Outline

1. Program Background
2. Introduction to Horizontal Directional Drilling (HDD)
3. Willamette River Crossing
4. Construction of HDD Segment
5. Acknowledgements
6. Questions



# Lake Oswego – Tigard Water Partnership





# Lake Oswego – Tigard Water Partnership

Population: 55,000  
Connections: 22,000  
ADD: 6.4 mgd  
PDD: 13 mgd  
King City, Durham, TWD


Population: 36,000  
Connections: 12,500  
ADD: 5.4 mgd  
PDD: 12 mgd  
Serves 5 wholesale customers



PDD  
16 mgd  
to  
38 mgd



# Program Overview - Existing Lake Oswego and Tigard Water Supply System



JAN. 27, 2010

# City of Lake Oswego's Infrastructure Needs

- 45+ year old system
- Structural deficiencies
- Obsolete equipment
- Critical lifelines





# Lake Oswego – Tigard Water Partnership

## Major Project Challenges

- A project completion span of eight-years from concept development.
- Construction within, across, and under a major river – home to endangered salmon and steelhead.
- Legal challenges from local project opponents and conservation groups.
- Project financing amidst recession and economic instability



# Lake Oswego – Tigard Water Partnership

## Major Project Challenges

- Construction of large diameter pipelines within and along narrow local roads in residential neighborhoods and across two major highways and railroads.
- Construction of a new water treatment facility located within a residential neighborhood.
- Maintaining full time operation of the existing WTP while the new WTP is constructed/expanded from 16 mgd to 38 mgd.
- Transitioning from the existing system to the new system.
- Property acquisition.





# Lake Oswego – Tigard Water Partnership


## Large Water Supply Pipeline

- Water from the Intake on the Clackamas River to Lake Oswego and Tigard
- Pipeline diameter ranges from 24 to 48 inches
- More than 10 miles
- This presentation focuses primarily on the trenchless pipeline crossing of the Willamette River



# Water System Improvements – Pipeline Status

## Spring 2016






# The Willamette River Crossing

- Trenchless Evaluation
  - Microtunneling
  - Horizontal Directional Drilling
- Geotechnical
- Schedule
- Environmental
- Easements
- Permitting
- Public Acceptability
- Constructability
- O&M Access
- Entry Area (shaft or mud pit)
- Exit Area (shaft or mud pit)
- Construction Access at the Entry/Exit
- Pipe Layout Area (HDD Only)







# Horizontal Directional Drilling




# Horizontal Directional Drilling



# Horizontal Directional Drilling Tracking



Tracking Systems typically accurate to within 2% of bore depth.



No surface coil or magnetic interference: use gyro steering tool



# Horizontal Directional Drilling

- Surface-to-surface installation
- Small mud pits
  - no deep/large excavations required
- Pressurized mud to cut a borehole
- Drilling mud stabilizes borehole
- Bore size increased by reaming
- Pulls assembled pipe into prepared bore
  - Preferably in one continuous pull
  - Conditions may dictate pulling in sections
- 2-inch to 48-inch commonly installed



# Horizontal Directional Drilling


- It's all about the MUD
- Run a Hydrofracture Analysis
  - Appropriate clearances below critical elements
- Conductor casings – proper installation
- Continuous pullback or analysis of bore stability



# The Willamette River Crossing – Route Selection

Design and Constructability Factors:

- Geotechnical
- Staging
- Ingress/Egress
- Pipe Pullback



**Selected Route: 3900 feet – OPRD to Meldrum Bar Park**

Permits:

- Federal
- State
- Local

Easements

- Permanent
- Temporary

Community Impacts






# The Willamette River Crossing Geotechnical Evaluation

OPRD / MSY – near surface sands, gravels

Meldrum Bar – gravels, cobbles



Rock strengths in basalt – 40,000+ psi



# Willamette River Crossing Pipe Material Selection for HDD

- **High Density Polyethylene (HDPE)**
  - 4-inch thick wall, 36-inch ID (44-inch OD)
  - Material homogeneity not guaranteed
- **Steel Pipe**
  - Fully Engineered Wall Thickness, Lining and Coating, Joint Type, High Tensile Strength (0.625 inch wall thickness)
  - 36-inch ID AWWA C200 Steel Pipe-- 37.25-inch OD
  - Polyurethane Lining (40 mils.) and Coating (80 mils.)
  - Full Penetration Butt Welded Joints
  - ROT: Bend Radius = 100 x (Nom. Diameter) inches = Bend Radius in Feet
  - For 36-inch Steel Pipe, Bend Radius = 3,600 feet




# Willamette River Crossing Steel Pipe Specified for HDD



## Steel Pipe Project Specifications

- Working Pressure: 150 psi
- Surge Pressure: 225 psi
- Full Vacuum (14.7 psi)
- Allowable Stress: 50% of Yield Strength of Steel
- Steel Coil Specified – ASTM A1018, GR 36, Structural Steel
- Min. Tensile Strength: 53 ksi
- 60-foot Sections of Pipe
- Lining & Coating: Polyurethane (40 mils & 80 mils), 1500 psi adhesion




**QUALITY CONTROL** - Tensile Test, Bend Test, Spot X-ray Tests, 10% X-ray Testing of Spiral Welds, Cylinders Hydro-tested to 75% of Yield





# Willamette River Crossing Construction of HDD Segment



OPRD

Meldrum Bar



Contractor installed a combination of telescoped conductor and wash-over (stabilizing) casings 14, 20, 54, and 60 inches in diameter, with the OPRD site (north of Mary S. Young Park) cased approximately 160 feet from ground surface and the Meldrum Bar Park site cased approximately 600 feet to bridge unstable soils



# Willamette River Crossing – Construction of HDD Segment




Pipe Ramming Used to Install 60-inch Conductor Casing




# Willamette River Crossing – Construction of HDD Segment

OPRD



Meldrum Bar



2 – 840,000 lb drill rigs

Final profile 80 feet  
below river bottom

9,000sf

12,000sf



10°



9°

## Intersect Method (x 2)



# Willamette River Crossing – Construction of HDD Segment

## BACK REAMING

- After 12.5-inch pilot hole complete
- Performed in 3 stages, 36-inch, 42-inch and 54-inch
- From OPRD site to Meldrum Bar Park site
- 1<sup>st</sup> Pass – 13 days, 242 feet/day
- 2<sup>nd</sup> Pass – 5 days, 630 feet/day
- 3<sup>rd</sup> Pass – 12 days, 263 feet/day
- 80-foot Section of 36-inch Pipe Passed through as Proof






# Willamette River Crossing – Construction of HDD Segment

## PIPE PREPARATION & PULLBACK

- 240-ft long sections of steel pipe were welded, as well as lining and coating joint completions performed in Advanced American Construction's yard near the St. John's Bridge, then transported approx. 18 river miles upstream via large derrick barge to Meldrum Bar Park





# Willamette River Crossing – Construction of HDD Segment

## PIPE PREPARATION & PULLBACK

- Each joint was butt-welded
- Surface prep inside and out w/ Surface Grinder (2 mils profile minimum)
- Testex Tape to Record Anchor Profile (ASTM procedure)
- Lining (40 mils) and Coating (80 mils) sprayed to same dry film thickness (DFT) as Pipe
- Adjacent Lining and Coating Feathered by Grinding
- Holiday Tested (for detection of discontinuities)
- Adhesion Values Tested



# Willamette River Crossing – Construction of HDD Segment


## PIPE PREPARATION & PULLBACK



# Willamette River Crossing – Construction of HDD Segment

## PIPE PREPARATION & PULLBACK

- Over a 10 day period, 16 sections of 240-long welded steel pipe were all welded together and joints completed
- Pipe floated into position and lofted over 100-ft into the air to achieve correct lineup and angle for the 54-inch borehole





# Willamette River Crossing – Construction of HDD Segment

## PIPE PREPARATION & PULLBACK





# Willamette River Crossing – Construction of HDD Segment

**PIPE PREPARATION & PULLBACK** (pullback completed in 14 hours)  
(overall approx. 100 days start to finish)





# Willamette River Crossing – Construction of HDD Segment

## SITE RESTORATION



Meldrum Bar site



OPRD site



# Acknowledgements

**OWNER: Lake Oswego – Tigard Water Partnership**

**PROGRAM MANAGEMENT: Brown and Caldwell**

**PIPELINE DESIGN: Kennedy/Jenks Consultants**

**TRENCHLESS DESIGN: Staheli Trenchless Consultants**

**PRIME CONTRACTOR:**

**Frank Coluccio Construction Company**

**TRENCHLESS CONTRACTOR:**

**Michels Directional Crossings**

**PIPE SUPPLIER: Northwest Pipe Company**





# Questions?

