

Willamette Water Supply

Our Reliable Water

Incorporating Additional Resilience Measures through
Operational and System Control Strategies now that the
Design is Complete for the Willamette Water Supply System

May 4, 2023

Michael Britch, P.E., MPA

Engineering and Construction Manager
Willamette Water Supply Program




PNWS-AWWA
Water 2023

Kennewick, WA • May 3-5

Outline

- WWSS Overview
- Level of Service and Time After Earthquake Event
- Timelines after Event
 - Earthquake
 - System Control
 - Power Supply
 - Capacity, Storage, and Hydraulics
 - People/Staff
 - Supplies and Infrastructure Interdependencies



Willamette Water Supply Program

Mission Statement: Provide a cost-effective, reliable and resilient water supply system by July 2026, that benefits current and future generations of the communities we serve and supports a vibrant local economy.




Image from the Regional Water Providers Consortium

Level of Service and Time After Earthquake Event¹


Level of Service Goals followed ***Oregon Resilience Plan*** Guidance (for Backbone Systems)

Performance Goals

Pressure Integrity

Operational Performance

Focused on controls for Facilities and Turnouts in this presentation




System Component	Capacity	Timing
Pipeline	80 – 90%	0 – 24 hours
Reservoirs	80 – 90%	0 – 24 hours
Turnouts	80 – 90%	0 – 24 hours
Raw Water Facilities	<u>25%</u> 50%	<u>24 hours</u> 48 hours
Treatment Plant	<u>25%</u> 50%	<u>24 hours</u> 48 hours


¹ Also considered infrastructure dependencies

Level of Service and Time After Earthquake Event

LOS Goals and
Time After
Earthquake Event
for Facilities and
Turnouts



Level of Service and Time After Earthquake Event



National Disaster
Recovery Framework
(Second Edition June 2016)





Figure 1: Recovery Continuum

Timeline After Event - Earthquake



Timeline After Event - Earthquake




Timeline After Event - Earthquake



Okawa primary school, where 74 children and 10 staff died in the tsunami in the 2011 Tohoku Earthquake

Timeline After Event - Earthquake



Historic Earthquakes Durations

- M 7.9 San Francisco (1906) – 45 sec
- M 6.6 San Fernando (1971) – 12 sec
- M 6.9 Loma Prieta (1989) – 20 sec
- M 6.7 Northridge (1994) – 10 – 20 sec
- M 8.0 Mexico City (1985) – 3 – 4 min
- M 9.1 Tohoku (2011) – 6 min
- M 9.2 Alaska (1964) – 4 ½ min


Subduction Zone Earthquakes

Timeline After Event – System Controls

Earthquake occurs

- Earthquake Response:

- Local accelerometer or “early warning system” provide signal
 - WWSS System Controls are initiated
 - Goal to get equipment to most stable state:
 - » Stop all mechanical systems
 - » De-energize all equipment
 - When external power supply stops, battery systems provide power to critical systems
 - Remain in stable state until post-earthquake critical activities complete




Observed seismic acceleration record in Sendai city (Nankodai Higashi elementary school) during the 2011 earthquake.

Mori, Tomohiro & Tobita, Yoshio & Okimura, Takashi. (2012). The damage to hillside embankments in Sendai city during The 2011 off the Pacific Coast of Tohoku Earthquake. Soils and Foundations. 52. 910–928. 10.1016/j.sandf.2012.11.011.

Timeline After Event – System Controls

- Post-Earthquake Activities (prior to energizing generators):
 - System hydraulic transients dissipate
 - Life safety/staff activities:
 - Individual safety
 - Staff safety check
 - Off-duty staff report in (as available)
 - Aftershocks
 - System Checks




Timeline After Event – System Controls


Automated Control Actions – Seismic Valves at Turnouts

- Turnouts supply water to Partner Agencies' systems

Autonomous Turnout Operations



1. Valve operation- automatically responds to seismic event (pre-selected response of closing, limiting or monitoring with limits)




Automated Control Actions – Seismic Valves at Turnouts



Timeline After Event – System Controls


Automated Control Actions – Seismic Valves at Turnouts



Timeline After Event – System Controls

Automated Control Actions – Seismic Valves at Turnouts

- PLC
- RTUs
- Accelerometer
- Battery Backup
 - 5 days for SCADA
 - 5 valve turns
- Hookup for temp power
- Information for control logic:
 - Communications from WTP
 - Local accelerometer
 - Local flow
 - Local downstream pressure



Timeline After Event – System Controls

Automated Control Actions – Seismic Valves at Turnouts

- Vital part of overall system operation:
 - Throttle flow
 - Maintain pressurized system
 - Preserve system storage
 - Continuity of system communications & control through SCADA with battery backup

*Requires 5 days of battery backup
(or alternate power supply) as part
of overall “System Operations”*





Figure 9. Effect of internal pressure on the bending response of double-welded lap joints ($D/t = 191$).



Timeline After Event – System Controls

Automated Control Actions – Seismic Valves at Water Treatment Plant




10 MG Clearwell and Finished Water Pump Station Under Construction



Tower Crane by UV Structure


Automated Control Actions – Seismic Valves at Water Treatment Plant



Within the main treatment process, seismic valves uses on the downstream side of the filters to keep them full of water on shutdown

Timeline After Event – System Controls

Automated Control Actions – Seismic Valves at Terminal Reservoirs





- Closure of seismic valves at turnouts need to be coordinated with remaining supply
- Seismic valve at reservoir closure driven by hydraulic transients




Timeline After Event – Power Supply

Grid
Power




Timeline After Event – Power Supply

Battery
Power



Timeline After Event – Power Supply


Generator
Power



Facilities with have several 2.5 to 3 MW generators



Timeline After Event - Capacity, Storage, and Hydraulics

Hydraulic
Transients




Timeline After Event - Capacity, Storage, and Hydraulics

Capacity



Timeline After Event - Capacity, Storage, and Hydraulics

Initial capacity based on available storage volume



Tentative Operational Levels:



Height (ft)	Elevation (ft)	Volume 1 Reservoir (MG)	Volume 2 Reservoirs (MG) [Future]	Comments
35	525	N/A	N/a	Roof Height
30	520	15	30	Top operational level
20	510	10	20	
10	500	5	10	Top emergency storage
0	490	0	0	Floor

Timeline After Event - Capacity, Storage, and Hydraulics

Available System Capacity

Time After Event	Capacity with 1 Reservoir*	Capacity with 2 Reservoirs*
0 – 24 hrs	5 mgd	10 mgd
24 – 48 hrs	15 mgd	15 mgd
48 hrs+	30 mgd	30 mgd
Power grid restored	60 mgd	60 mgd


* Based on initial WTP capacity of 60 mgd




Timeline After Event – System Controls

Automated Control Actions – Seismic Valves at Turnouts

Turnout Control Logic (Tentative)



Closure of Motorized Seismic Valve in Turnout Flow Meter Vault




Timeline After Event – System Controls

Automated Control Actions – Seismic Valves at Turnouts


Longest Valve Closure Time

Butterfly valve starts in *fully* open position

Start position
fully open
(Position A)



End position
(Position B)




Valve moves almost 90°
to nearly closed position


Optimized Valve Closure Time

Butterfly valve starts in *partially* open position

Start position
partially open
(Position A)




End position
(Position B)




5 mgd system flow

24 hr position
(Position C)



15 mgd system flow

48 hr position
(Position D)




30 mgd system flow

Valve closure times need to be coordinated
with hydraulic transient response of system

Timeline After Event – People/Staff

Initially
Shelter
in Place



Timeline After Event – People/Staff


System Checks

- Through SCADA and control systems
- Though instrumentation
- Visual
 - “Rapid” inspection (OrSAP training – June 7)
 - Remote through video cameras





Timeline After Event – People/Staff

Request
Supplies
&
Emergency
Response
Coordination



Timeline After Event – People/Staff


- Coordination and reporting out to Partner Agencies and coordination with other emergency response activities



Time After Event - Supplies and Infrastructure Interdependencies


“Action Plan” included in County’s Natural Hazard Mitigation Plan (NHMP) related to Seismic Upgrade to Two Bridges on Roy Rogers Road:

- Serves as a critical transportation link within Washington County to provide supplies for WTP and RWF operations following an earthquake.



WWSP Seismic Level of Service (LOS) Goals

- Target States of Recovery modeled off the ORP
- Added “5 days of self-sufficiency”



	Event occurs	0-24 hours	1-3 days	3-7 days	1-2 weeks	2 weeks-1 month	1-3 months	3-6 months	6 months-1 year	1-3 years	3+ years
Domestic Water Supply											
Potable water available at supply source (WTP, wells, impoundment)		R	Y		G			X			
Main transmission facilities, pipes, pump stations, and reservoirs (backbone) operational		G					X				
Water supply to critical facilities available		Y	G				X				
Water for fire suppression—at key supply points		G		X							
Water for fire suppression—at fire hydrants				R	Y	G			X		
Water available at community distribution centers/points			Y	G	X						
Distribution system operational			R	Y	G				X		




Turnouts also part of maintaining 5 days of operational capacity of the WWSS overall “System Operations”

Table 4-2 WWSP LOS Goals

System Components	Proposed
Intake and RWF	<ul style="list-style-type: none"> • 25% capacity within 24 hours • 50% capacity within 48 hours • 90% to full capacity when power transmission and transportation is restored • 5 days of self-sufficiency for all consumables required for operations • Fire suppression systems shall be autonomous and fully operable at 90-100% capacity immediately after a seismic event
WTP	<ul style="list-style-type: none"> • 25% capacity within 24 hours • 50% capacity within 48 hours • Full treatment process available immediately for critical components⁷ • 90% to full capacity when power transmission and transportation is restored • 5 days of self-sufficiency for all consumables required for operations • Fire Suppression systems shall be autonomous and fully operable at 90-100% capacity immediately after a seismic event
Terminal Storage Reservoir	<ul style="list-style-type: none"> • Same as ORP, Main Transmission System • RES_1.0 Water Quality Building and related infrastructure shall meet the requirements of other “Facilities” as identified for the “Intake and RWF” and the “WTP”
Transmission Lines	<ul style="list-style-type: none"> • Same as ORP, Main Transmission System
Appurtenances	<ul style="list-style-type: none"> • Same as ORP, Main Transmission System
Turnouts	<ul style="list-style-type: none"> • Same as ORP, Main Transmission System
System Communications	<ul style="list-style-type: none"> • All critical systems to be hardwired • All critical systems must be able to operate independent of Internet (including wireless) • Include cyber security protocols
Distributed Control System	<ul style="list-style-type: none"> • Primary and secondary communication systems to be determined
System Infrastructure	<ul style="list-style-type: none"> • All facilities and transmission system components shall sustain no structural or mechanical damage that impairs system capacity or operability

Key: ORP = Oregon Resilience Plan; RWF = Raw Water Facilities; WTP = Water Treatment Plant

Time After Earthquake Event



Mike Britch, P.E., MPA

Engineering and Construction Manager

Willamette Water Supply Program

mike.britch@tvwd.org



info@ourreliablewater.org

www.ourreliablewater.org

EXTRA SLIDES

C.A.T.S. System

- <https://youtu.be/wmOmlrsZQk0>